VALUE ENGINEERING CHANGE PROPOSAL MISSOURI DEPARTMENT OF TRANSPORTATION

	Date 4/19/10
Contract ID 100122-202	Job No. <u>J2P0779C</u>
County RANDOLPH	24 Original Bid Cost \$ 2,012,213.80
Contractor APAC-MISSOURI, INC.	By DAVID B. TAG, P.E.
Designed By _APAC-MISSOURI, INC.	Phone (573) 449-0886
VECP# 10-44 (to be completed	by C.O.) VECP or VECP/PDU
The current plan is to perform the u 4 separate 5-day periods. This VE closing the adjacent section of Busadvantages of this are labor and eque coldmilling, geotextile, and overlay weeks to 2 weeks. The disadvantage	and proposed change(s). Advantages/Disadvantages inbonded overlay of the Bus. 367 24 intersection is 4 stages over Proposal is to perform the overlay in 2 stages rather than 4 by .63 while each half of Route 24 is being overlaid. The aipment savings by combining two activities into one for the y. Also, the total duration of the project will be reduced from 4 ges are a road closure that limits local access to Route 24.
2. Estimate of reduction in construction	costs. \$30,284.00 A detailed summary is attached.
maintenance and operations. MoDOT will have increased public Route 24 for 2 weeks.	change(s) will have on other department costs, such as relations duties as a result of limiting Bus. Route 63 access to ailed change(s) of items required by Section 104.6 of the
·	April 19, 2010
	(date)
5. Deadline for issuing a change order to contract completion time or delivery s	o obtain maximum cost reduction, noting the effect of schedule.
April 30, 2010	Field Surveying will be modified if staging is changed
(date)	(effect)
6. Dates of any previous or concurrent s	ubmission of the same proposal.
	None
	(date and/or dates)

Addi	tional Comments:		
	-	litional CMS boards or construction signs if necessary	to designate the road
closu	re.		
	** Port	tion Below This Line To Be Filled Out by MoDOT *	**
C			
 	matter how this intersection i	d be approved based on the cost savings and the decreased co is constructed there will be substantial inconvenience to the tra used by constructing this area in two parts rather than four is fa on time.	aveling public. I feel that
		Jeff Gander	4/29/2010
		Submitted By Resident Engineer	Date
	ments:	and the second s	tu u vontanas ta la sal
moi traf	torists, but there are good alt fic through the intersection a	losure of this intersection to North/South traffic will be a major ternate routes (state and city) for that movement. The proposal at all times, which is important since there are no other reasonal in addition to being less costly, this proposal would cut the co	maintains East/West ble detours that can
X	Approval Recommended _	Dan Niec	4/29/2010
	Rejection	District Engineer	Date
<u> </u>	Recommended		
Comi	ments:		
Com	ments.		
	Approval Recommended		
	Rejection Recommended	Federal Highway Administration Required for FHWA Full Oversight Projects	Date
Com	ments:) - 4/30/2010	

Resident Engineer, Project Manager, District Construction & Materials Engineer, State Construction & Materials Engineer, Value Engineering Administrator – MoDOT, P. O. Box 270, Jefferson City, MO 65102 Distribution:

State Construction and Materials Engineer

Date

Approval

Rejection

									_
Co., - J2P0779C - VE Proposal #2 Item Summary 2 Stages		What will be saved	145,705.54 Existing Item - Cost for 4 stages of construction	36,833.52 Existing Item - Cost for 4 stages of construction	16,198.16 Existing Item - Cost for 4 stages of construction	18.35 \$ (127,561.86) New Item - Cost for 2 stages of construction	(25,805.52) New Item - Cost for 2 stages of construction	(15,085.84) New Item - Cost for 2 stages of construction	
#2 Item Su		Saved	145,705.54	36,833.52	16,198.16	(127,561.86)	(25,805.52)	(15,085.84)	30,284.00
sal			\$	\$	\$	\$	\$	\$	\$
E Propos		New Cost				\$ 18.35	\$ 3.51	\$ 2.17 \$	TOTAL
779C - V		Cost	3 20.96	5.01	3 2.33				
2P0		jį į	8	} }	7	<u> </u>	۸ ـ	٨	_
بل.		Unit	λS	λS	λS	λs	Ś	S	
_		Qty. affected	6951.6	7352	6952	6951.6	7352	2369	
Route 24, Randolph	Items to be affected	Item Description	Unbonded Concrete Overlay	Coldmilling >3" Thick	Geotextile Fabric, Type 1	Unbonded Concrete Overlay	Coldmilling >3" Thick	Geotextile Fabric, Type 1	
		Item #	90	270	290	200X	500X	200X	

VE SPLIT \$ 15,142.00



An Oldcastle Company

Friday, April 23, 2010

Mr. Jeffrey L. Gander, R.E. MoDOT Macon Project Office 26824 US Highway 63 P.O. Box 254 Macon, MO 63552

RE:

Rte, 24, Randolph County

Job No. J2P0779C & J2P0779D

Contract ID: 100122-202

Dear Mr. Gander:

Here are the additional details you have requested concerning the VE Proposal on the above referenced project:

- Yes JSP N and JSP O should be changed by replacing the word "quadrants" with the word "halves".
 We intend to perform this work within the 5 calendar days specified and do expect LD's to be charged after 5 calendar days.
- 2) This VE savings is created by combining two quadrants of work into one continuous operation which creates the labor and equipment savings which allows for the lower unit prices. I do not expect quantities to change by this VE. Here is a breakdown of these costs for your information:

Project Mobilization

There is no savings to project mobilization since that cost is to transport the equipment to the site from Columbia or another project and back to Columbia or another project. Modifying the duration of the project from 4 weeks to 2 weeks does not reduce our trucking costs since the equipment would not leave the site. It does affect the coldmilling mobilization, but that cost is charged to the milling item and will be reflected in the savings of the milling item cost reduction.

Item 80 - Unbonded Concrete Overlay

This is the cubic yard item. It contains only concrete material cost. There will be no changes to the amount of material required and no changes to this item.

Item 90 – Unbonded Concrete Overlay Placing

This item contains the labor and equipment necessary to perform the overaly. The original plan was 3.5 shifts per quadrant (140 crew hours in total for 4 quadrants x 3.5 shifts per quadrant x 10 hours per shift) with a crew comprised of 1 foreman, 2 carpenter, 2 skilled laborers, 4 general laborers, and 1 operator with 1 boom truck at 50% utilization, 1 concrete finishing machine with 33% utilization, 1 portable generator with 100% utilization, 4 light plants with 85% utilization, 1 pickup truck with 100% utilization, 1 rubber tire loader with 42% utilization, and 1 water truck with 25% utilization. This was based upon a 5 day-10 hour calendar for overtime calculations.



1591-A East Prathersville Road Columbia, MO 65202 P.O. Box 1117 Columbia, MO 65205 Tel: 573 449-0886 Fax: 573 449-2980 www.apacmo.com





APAC-Missouri, Inc.

1591-A East Prathersville Road Columbia, MO 65202 P.O. Box 1117 Columbia, MO 65205 Tel: 573 449-0886 Fax: 573 449-2980 www.apacmo.com

The VE proposal will not change the make-up of the crew or equipment needed to perform the work. My expectation of savings is based upon performing the work in 5.5 shifts per half, a savings through efficiency of 1.5 shifts per half with a total reduction in labor and equipment of 3.0 shifts, or 30 crew hours (21% reduction in labor and equipment costs). The only upcharge was a modification from the 5 day-10 hour calendar to a 6 day-12 hour calendar for overtime calculations due to the increased magnitude of work to be completed within a 5 calendar day period which would require additional overtime to complete each task and reduced flexibility in the scheduling of the work. The upcharge for this was approximately \$3,000 per half. The total net savings from the labor and equipment for this item was \$18,144 which compares well to the approximate \$750 / hour cost of the crew represented in the 30 crew-hour reduction.

This item also contained the cost of the overlay accessories, sundry materials, and subcontractor

sawing, which will not be affected by this VE proposal.

With this letter APAC-Missouri, Inc. submits a modification in the unit price of this item from \$20.96 / SY to \$18.35 / SY with the accepted VE proposal.

Item 270 - Coldmilling >3" Thick

This item had two activities – mobilization and milling. The original activity for mobilization to the site allowed for 4 mobilizations in 12 crew hours made with 4 permits, 2 operators, 1 foreman, 1 driver, 1 tractor-trailer, 1 service truck, and 1 pickup for a total cost of \$5,000. The VE proposal will reduce this to a 2 mobilization requirement, cutting all of the above in half for a savings of \$2,500.

The milling operations crew is 1 foreman, 2 drivers, 2 general laborers, and 3 operators with 1 pickup truck, 1 broom, 1 milling machine, 1 skid steer, 1 street sweeper, and 1 service truck at an approx. cost of

\$1,250 per hour.

The plan activity for the 7352 SY of milling was 26 crew hours – 2 hours for the 400 SY at the RR bridge and 6 hours per quadrant. The VE proposal to halves will reduce this to 20 crew hours – 2 hours for the 400 SY at the RR bridge and 9 hours per half, creating a savings of 6 crew hours or approximately \$7,500. There is also a reduction in the cost of trucking for milled material from 100 truck-hours to 90 truck-hours with a savings of \$1,000.

The total savings from the labor and equipment for this item was \$11,028. With this letter APAC-Missouri, Inc. submits a modification in the unit price of this item from \$5.01 / SY to \$3.51 / SY with the

accepted VE proposal.

Item 290 - Geotextile Fabric, Type 1

The installation of the geotextile fabric was originally planned with 3 general laborers in 8 hours per quadrant for a total of 32 crew hours. The VE proposal is expected to reduce this to 12 hours per half for a total of 24 crew hours. This 25% reduction in labor results in a savings of \$1,100. With this letter APAC-Missouri, Inc. submits a modification in the unit price of this item from \$2.33 / SY to \$2.17 / SY with the accepted VE proposal.

The total savings generated by this VE proposal is \$30,284 to be split 50-50 between APAC-Missouri, Inc. and MoDOT.





APAC-Missouri, Inc.

1591-A East Prathersville Road Columbia, MO 65202 P.O. Box 1117 Columbia, MO 65205 Tel: 573 449-0886 Fax: 573 449-2980 www.apacmo.com

3) Here is a step-by-step process from which each half will be constructed:

ONE HALF OF INTERSECTION

- Install the traffic control to keep traffic out of the work area.
- Set string lines for milling control on Route 24
- Mill Route 24 to the desired profile end to end
- Set string lines for milling control on Bus. 63
- Mill Bus. 63 to the desired profile end to Route 24
- Clean the milled surface of Route 24
- Install geotextile on Route 24
- Mill the two turning radii from island to edge line
- Clean the milled surface of Bus. 63 and radii
- Install geotextile on Bus. 63 and radii
- Set the paving string lines along Route 24 end to end
- Set the paving rail and paving machine on Route 24 end to end and check paving thicknesses
- Pour the unbonded overlay on Route 24 end to end
- Saw the joints in the overlay on Route 24 end to end
- Remove the paving string line and paving rails from Route 24
- Set the paving string lines along Bus. 63 end to Route 24
- Set the paving rail and paving machine on Bus. 63 end to Route 24 and check paving thicknesses
- Pour the unbonded overlay on Bus. 63 end to Route 24
- Saw the joints in the overlay on Bus. 63 end to Route 24
- Remove the paving string line and paving rails from Bus. 63
- Set the paving rails on the radii
- Pour the unbonded overlay on the radii
- Saw the joints in the overlay on the radii
- Cleanup concrete surface on Route 24, Bus. 63, and radii
- Remove equipment and supplies from the work area
- Ensure final strength necessary to open the roadway to traffic
- If necessary, place temporary asphalt wedges to bridge traffic onto new concrete from old roadway
- Remove the traffic control or switch the traffic control to the next half open new concrete to traffic
- 4) I do not anticipate any additional signs or traffic control devices necessary for the work area. Simply put, the only modification to the traffic control plan will be to not allow right turns into the work area from Route 24 or through traffic on Bus. 63 into the work area. This will be done with channelizers and barricades in nearly the same configuration. I have provided a sketch with this letter as a suggestion, but the traffic control plan to be used must be provided by MoDOT.
- 5) I don't have an objection to a lump sum modification to the contract based upon the price reductions and VE split.





APAC-Missouri, Inc.

1591-A East Prathersville Road Columbia, MO 65202 P.O. Box 1117 Columbia, MO 65205 Tel: 573 449-0886 Fax: 573 449-2980

www.apacmo.com


I expect to send the details of the proposed alignment from Crocket Engineering for your review later today. If there are any other details I can provide at this time, please call me at 573-228-7078.


Sincerely,

APAC-Missouri, Inc.

David B. Tag, P.E. Area Manager APAC-Missouri, Inc.

CC: Jobfile





TYPE OF WORK

(Check one that applies)

- □ Bridge/Structure/Footings
- □ Drainage Structures (RCP, RCB, CMP's, ect.)

TCP/MOT

- □ Paving (PCCP, ect.)
- □ Grading/MSE Walls
- □ Signal/Lighting/ITS
- □ Misc.

SUMMARY OF PROPOSAL

(If needed, condense summary to a couple of lines)

THIS VE SIMPLIFIES TRAFFIC CONTROL BY SPLITTING
THE WORK INTO HALVES, INSTEAD OF QUARTERS, AND
REDUCING THE WORK SCHEDULE. CLOSURE OF BUS 63
WILL BE NECESSARY DURING CONSTRUCTION, HOWEVER.

SCANNING OF DOCUMENT

				ote, whi m here.	ges nec	ed to b	e scar	ined i	nto the o	database.	If
	 	 	 	 	 	eren i anam ana an					